

CONSTRUCTION PLANS FOR LOWER SAND CREEK CORRIDOR RESTORATION PROJECT

PREPARED FOR COON CREEK WATERSHED DISTRICT

JULY 2018



SHEET INDEX						
SHEET	TITLE					
G-101	TITLE AND INDEX SHEET					
G-102	LEGEND AND GENERAL NOTES					
C-101	REMOVALS PLAN					
C-102	REMOVALS PLAN					
C-103	PROPOSED PLAN & PROFILE STREAM TREATMENTS					
C-104	PROPOSED PLAN & PROFILE STREAM TREATMENTS					
C-105	PROPOSED PLAN & PROFILE STREAM TREATMENTS					
EC-101	SWPPP					
D-101	DETAILS					
D-102	DETAILS					
D-103	DETAILS					
	THIS PLAN CONTAINS 11 SHEETS					



WARNING:

THE CONTRACTOR SHALL BE RESPONSIBLE FOR CALLING FOR LOCATIONS OF ALL EXISTING UTILITIES. THEY SHALL COOPERATE WITH ALL UTILITY COMPANIES IN MAINTAINING THEIR SERVICE AND/OR RELOCATION OF LINES.

THE CONTRACTOR SHALL CONTACT GOPHER STATE ONE CALL AT 651-454-0002 AT LEAST 48 HOURS IN ADVANCE FOR THE LOCATIONS OF ALL UNDERGROUND WRES, CABLES, CONDUITS, PIPES, MANHOLES, VALVES OR OTHER BURIED STRUCTURES BEFORE DIGGING. THE CONTRACTOR SHALL REPAIR OR REPLACE THE ABOVE WHEN DAMAGED DURING CONSTRUCTION AT NO COST TO THE OWNER.

CALL BEFORE YOU DIG GOPHER STATE ONE CALL

TWIN CITY AREA: 651-454-0002
TOLL FREE 1-800-252-1166

PROJECT VICINITY MAP

3	FOR BIDDING	SJB	EAM	07/25/18	
2	90% DESIGN	SJB	EAM	06/12/18	
1	60% DESIGN	LNJ	EAM	12/20/17	
0	CONCEPT DESIGN	SJB	EAM	02/02/17	
REV	REVISION DESCRIPTION	DWN	APP	REV DATE	

PRIME CONSULIANT
WENCK
ASSOCIATES
Responsive partner. Exceptional outcomes.

PROJECT TITLE	SHEET	TIT
LOWER SAND CREEK CORRIDOR RESTORATION		
	i	

TITLE AND INDEX SHEET

COON CREEK WATERSHED DISTRICT SJE

12301 CENTRAL AVE NE. SUITE 100
RIAINE MN 55434

GENERAL NOTES:

- EXISTING CONDITIONS HAVE BEEN PROVIDED BY A COMBINATION OF HISTORIC PLANS FROM SURVEY INFORMATION FROM A SITE VISIT BY WATERSHED DISTRICT STAFF AND LIDAR. EXISTING FEATURES MAY NOT BE EXACT TO THEIR LOCATION. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE CONDITIONS OF THE SITE AND SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES OR VARIATIONS FROM THE DRAWINGS.
 ALL QUANTITIES ARE APPROXIMATE AND MAY VARY TO ALLOW COMPLETION OF WORK.
- THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D. THIS QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38-2 ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEPICTION OF EXISTING SUBSURFACE UTILITY DATA".
- SUBSURFACE UTILITY DATA:

 EXACT LOCATION OF UNDERGROUND UTILITIES SUCH AS GAS, TELEPHONE, FIBER OPTIC, PIPELINES, ELECTRICAL, AND CABLE TV ARE UNKNOWN. CONTRACTOR RESPONSIBLE FOR LOCATING PRIOR TO STARTING WORK.

 CONTRACTOR SHOULD ANTICIPATE PRIVATE UTILITY CONFLICTS THROUGHOUT THE PROJECT
- CONTRACTOR SHOULD ANTICIPATE PRIVATE UTILITY CONFLICTS THROUGHOUT THE PROJECT SUB CUT AND TRENCH AREAS AND SHALL COORDINATE WITH PRIVATE UTILITY OWNERS. THE RELOCATION AND OR PROTECTION OF ALL EXISTING UTILITIES MUST BE COORDINATED BY THE CONTRACTOR AND ANY COSTS FOR SUCH WORK SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR EXTRA TIME AND EFFORT OF PROVISIONS NECESSARY TO WORK AROUND OR UNDER ANY UTILITIES. INSTALL AND MAINTAIN EROSION CONTROL DEVICES AS SPECIFIED OR AS DIRECTED BY
- FNGINFFR.
- ENGINEER.

 8. CONTRACTOR SHALL COMPLY WITH ALL STATE, COUNTY, AND CITY PERMITS.

 9. MAINTAIN MAIL, GARBAGE, AND RECYCLING SERVICES TO PROPERTIES.

 10. PROTECT EXISTING PAYEMENT AND SITE FEATURES, EXCEPT AS NOTED.
- 11. CONTRACTOR TO COORDINATE AND MAINTAIN ACCESS TO PROPERTIES.
- 12. MAINTAIN DRAINAGE CONVEYANCE DURING CONSTRUCTION (BOTH PIPED AND OVERLAND).

 13. THE EXISTING PAVEMENT CONDITIONS HAVE BEEN DOCUMENTED, AND ANY DAMAGE TO THE EXISTING PAVEMENT, CURBING, AND STRIPING SHALL BE REPLACED BY THE CONTRACTOR, TO THE OWNERS SATISFACTION, AT NO ADDITIONAL COST TO THE OWNER.

REMOVAL NOTES:

FEATURES NOT SPECIFICALLY IDENTIFIED ON PLAN FOR SALVAGE OR REMOVAL THAT CONFLICT WITH CONSTRUCTION ARE TO BE REVIEWED WITH ENGINEER.

DEWATERING NOTES:

- NO BID ITEM HAS BEEN PROVIDED FOR DEWATERING AS ALL DEWATERING WORK NECESSARY FOR CONSTRUCTION WILL BE CONSIDERED INCIDENTAL.
- ENERGY DISSIPATION SHALL BE PROVIDED AT ALL DISCHARGE POINTS TO
- PREVENT SCOUR.

 PROVIDE SILT BACS FOR DEWATERING.

 CONTRACTOR RESPONSIBLE TO SUBMIT DEWATERING PLAN TO ENGINEER FOR REVIEW. DEWATERING SHALL MEET ALL PERMIT REQUIREMENTS AND BE APPROVED PRIOR TO STARTING ANY CONSTRUCTION ACTIVITIES.

 THE CONTRACTOR MUST DISCHARGE TURBID OR SEDIMENT—LADEN WATER RELATED TO
- THE CONTRACTOR MUST DISCHARGE TURNID OR SEDIMENT—LABOR WATER RELATED TO DEWATERING OR BASIN DRAINING (E.G. PUMPED DISCHARGES, TRENCH/DITCH CUTS FOR DRAINAGE) TO A TEMPORARY OR PERMANENT SEDIMENTATION BASIN ON THE PROJECT SITE UNLESS INFEASIBLE. THE CONTRACTOR MAY DISCHARGE FROM THE TEMPORARY OR PERMANENT SEDIMENTATION BASINS TO THE SURFACE WATERS IF THE BASIN WATER HAS BEEN VISUALLY CHECKED TO ENSURE ADEQUATE TREATMENT HAS BEEN OBTAINED IN THE BESIN AND THAT NUISANCE CONDITIONS (SEE MINN. RULES 7050.0210, SUBPART 2) WILL NOT RESULT FROM THE DISCHARGE. IF THE WATER CANNOT BE DISCHARGED TO A SEDIMENTATION BASIN PRIOR TO ENTERING THE SURFACE WATER, IT MUST BE TREATED WITH THE APPROPRIATE BMPs, SUCH THAT THE DISCHARGE DOES NOT ADVERSELY AFFECT THE RECEIVING WATER OR DOWNSTREAM PROPERTIES. IF THE CONTRACTOR MUST USE AN DISCHARGE WATER THAT CONTAINS OIL OR GREASE, THE CONTRACTOR MUST USE AN DISCHARGE PROPERTIES. OIL-WATER SEPARATOR OR SUITABLE FILTRATION DEVICE (E.G. CARTRIDGE FILTERS. ABSORBENTS PADS) PRIOR TO DISCHARGING THE WATER. THE CONTRACTOR MUST ENSURE THAT DISCHARGE POINTS ARE ADEQUATELY PROTECTED FROM EROSION AND SCOUR. THE
- DISCHARGE MUST BE DISPERSED OVER NATURAL ROCK RIPRAP, SAND BAGS, PLASTIC SHEETING, OR OTHER ACCEPTED ENERGY DISSIPATION MEASURES.
 ALL WATER FROM DEWATERING OR BASIN-DRAINING ACTIVITIES MUST BE DISCHARGED IN A MANNER THAT DOES NOT CAUSE NUISANCE CONDITIONS, EROSION IN RECEIVING CHANNELS
- MANNER THAT DOES NOT CAUSE NUISANCE CONDITIONS, EROSION IN RECEIVING CHANNEL OR ON DOWNSLOPE PROPERTIES, OR INUNDATION IN WETLANDS CAUSING SIGNIFICANT ADVERSE IMPACT TO THE WETLAND.

 IF THE CONTRACTOR IS USING FILTERS WITH BACKWASH WATER, THE CONTRACTOR MUST HAUL THE BACKWASH WATER AWAY FOR DISPOSAL, RETURN THE BACKWASH WATER TO THE BEGINNING OF THE TREATMENT PROCESS, OR INCORPORATE THE BACKWASH WATER INTO THE SITE IN A MANNER THAT DOES NOT CAUSE EROSION. THE CONTRACTOR MAY DISCHARGE BACKWASH WATER TO THE SANITARY SEWER IF PERMISSION IS GRANTED BY THE SANITARY SEWER IF PERMISSION IS GRANTED BY THE SANITARY SEWER IF DEFINISSION IS GRANTED BY THE SANITARY SEWER IF DEFINISSION IS GRANTED BY THE SANITARY SEWER IF DEFINISSION IS GRANTED BY THE SANITARY SEWER IN PROMISSION OF THE PROPERTY OF T FILTER MEDIA USED IN DEWATERING DEVICES WHEN REQUIRED TO RETAIN ADEQUATE

WARNING:

THE CONTRACTOR SHALL BE RESPONSIBLE FOR CALLING FOR LOCATIONS OF ALL EXISTING UTILITIES. THEY SHALL COOPERATE WITH ALL UTILITY COMPANIES IN MAINTAINING THEIR SERVICE AND/OR RELOCATION OF LINES.

THE CONTRACTOR SHALL CONTACT GOPHER STATE ONE CALL AT 651-454-0002 AT LEAST 48 HOURS IN ADVANCE FOR THE LOCATIONS OF ALL UNDERGROUND WIRES, CABLES, CONDUITS, PIPES, MANHOLES, VALVES OR OTHER BURIED STRUCTURES BEFORE DIGGING. THE CONTRACTOR SHALL REPAIR OR REPLACE THE ABOVE WHEN DAMAGED DURING CONSTRUCTION AT NO COST TO THE OWNER.

CALL BEFORE YOU DIG GOPHER STATE ONE CALL

TWN CITY AREA: 651-454-0002

GOVERNING SPECIFICATIONS:

- 1. THE MINNESOTA DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION" 2016 EDITION & LATEST SUPPLEMENTS.
- 2. CITY ENGINEERS ASSOCIATION OF MINNESOTA (CEAM) STANDARD LITHIUTIES
- SPECIFICATIONS (LATEST EDITION)
 CITY OF COON RAPIDS CONSTRUCTION SPECIFICATIONS
- ALL APPLICABLE FEDERAL, STATE AND LOCAL LAWS AND ORDINANCE WILL BE COMPLETED WITH IN THE CONSTRUCTION OF THIS PROJECT.

TRAFFIC CONTROL NOTES:

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL CONSTRUCTION STAGING, ON OR OFFSITE, AS NECESSARY TO COMPLETE THE WORK AS SPECIFIED IN THE PROJECT DOCUMENTS. A STAGING PLAN SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL PRIOR TO ANY CONSTRUCTION RELATED ACTIVITIES.

 CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRAFFIC CONTROL. ALL TRAFFIC CONTROL SHALL CONFORM TO THE LATEST EDITION OF THE MMUTCD, INCLUDING THE LATEST FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS. A TRAFFIC CONTROL PLAN SHALL BE SUBMITTED TO THE ENGINEER, CITY, AND COUNTY FOR REVIEW AND APPROVAL PRIOR TO ANY CONSTRUCTION RELATED ACTIVITIES. PLANS SHALL COMPLY WITH ALL APPLICABLE PERMIT REQUIREMENTS.
- PRIOR TO ANY CONSTRUCTION RELATED ACTIVITIES. PLANS SHALL COMPLET WITH ALL APPLICABLE PERMIT REQUIREMENTS.

 TRAFFIC CONTROL SHALL ALSO INCLUDE ALL NECESSARY SIGNAGE AND MARKINGS REQUIRED FOR THE BOARDWALK CLOSURE (SIMILAR TO SIDEWALK CLOSURE). THIS SHALL INCLUDE ADVANCED WARNING SIGNS AND NECESSARY FENCING AND SIGNAGE TO PREVENT PEDESTRIANS FROM ACCESSING THE PROPOSED BOARDWALK CONNECTION AREA.

EROSION CONTROL NOTES:

- SEE SHEETS EC-101 FOR EROSION AND SEDIMENT CONTROL MEASURES.
 ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED DEPENDING ON SITE
 CONDITIONS DISING CONSTRUCTION. COORDINATE WITH ENGINEER.
 CONCRETE WASH-OUT SHALL COMPLETED OFF-SITE OR CONCRETE READY MIX TRUCKS
 SHALL BE SELF-CONTAINED.
 ALL EROSION CONTROL DEVICES TO BE INSTALLED PRIOR TO COMMENCEMENT OF WORK,
 MAINTAINED IN ACCORDANCE WITH THE SWPPP, NPDES, AND SPECIFICATIONS THROUGHOUT
 DURATION OF PROJECT, AND REMOYED UPON ESTABLISHMENT OF FINAL STABILIZATION AS
 DIRECTED BY ENGINEER. EROSION CONTROL MEASURES USED FOR CONSTRUCTION SHALL
 NOT BE REMOYED UNTIL AUTHORIZED BY OWNER OR ENGINEER.
- REMOVE TRACKED SEDIMENT FROM ALL PAVED SURFACES BOTH ON AND OFFSITE ON A
- DAILY BASIS (INCIDENTAL).

 6. MINIMIZE DUST FROM CONSTRUCTION OPERATIONS BY PROVIDING WATER OR OTHER APPROVED METHOD ON A DAILY BASIS (INCIDENTAL).

HORIZONTAL AND VERTICAL CONTROL:

- THE HORIZONTAL CONTROL FOR THIS PLAN IS ANOKA COUNTY COORDINATE
- RELATIVE TO SYSTEM NAD83(11).
 2. THE VERTICAL CONTROL FOR THIS PLAN IS NAVD88.

<u>ABBRE</u>	<u> VIATIONS</u>	EXISTING SY	MBOLS/LINES LEGEND
BV	BUTTERFLY VALVE	₽	STORM SEWER FLARED END SECTION
©	CENTER LINE		STORM SEWER CATCH BASIN/MANHOLE
CL.	CLASS		
CMP	CORRUGATE METAL PIPE	>>	STORM SEWER
CY	CUBIC YARD	>	HYDRANT
DIP	DUCTILE IRON PIPE		WATER MAIN
EL./ELEV	ELEVATION		<u></u>
EX	EXISTING	— — 898 — —	CONTOUR MINOR
FES	FLARED END SECTION	— — 900 — —	CONTOUR MAJOR
F/F	FACE TO FACE		PROPERTY LINE
FM	FORCEMAIN		THOSE ENTERNAL
GV	GATE VALVE		PROJECT AREA LIMITS
HDPE	HIGH-DENSITY POLYETHYLENE		ACCESS ROUTE BOUNDARY
HP	HIGH POINT		
HWL	HIGH WATER LEVEL		RETAINING WALL
HYD	HYDRANT	X	EXISTING FENCE
INV	INVERT		EXISTING CHANNEL
LF	LINEAL FEET		
LP	LOW POINT	./ 1 1 1	APPROXIMATE TREE LINE
МН	MANHOLE	WET	WETLAND BOUNDARY
NWL	NORMAL WATER LEVEL	_	
PVC	POLYVINYL CHLORIDE	0	DECIDUOUS TREE
R	RADIUS	⊠ PP N_S	UTILITY POLE
RCP	REINFORCED CONCRETE PIPE	×	LIGHT POLE
R/W	RIGHT-OF-WAY		EDGE OF PAVEMENT
SF	SQUARE FEET		
STA	STATION	Δ	SIGN
SY	SQUARE YARD	MB	MAILBOX
TNH	TOP NUT HYDRANT	4	GUARD POST
TYP	TYPICAL	•	SUNID 1 USI
WM	WATERMAIN	•	PROPERTY IRON

PROPOSED SYMBOLS/LINES LEGEND

STORM SEWER FLARED END SECTION

RIP RAP

STORM SEWER CATCH BASIN/MANHOLE

->>- ___>_ DRAINTILE

· VEGETATED RIPRAP

HILLIH LOG TOF WITH ROOT WADS

//////// BACKWATER POOL - CONTOUR MINOR

— CONTOUR MAJOR

£811.95 BITUMINOUS

SPOT ELEVATION

CONCRETE \bigcirc XXX DECIDUOUS TREE ---- ACCESS ROUTE BOUNDARY

— — — PROPERTY LINE

— WATER EDGE

- PROPOSED CHANNEL CENTERLINE - - PROJECT AREA LIMITS

REMOVAL SYMBOLS/LINES LEGEND



TREE REMOVAL

EROSION CONTROL SYMBOLS/LINES LEGEND

EROSION CONTROL BLANKET AND MN SEED MIX 34-262

HYDROMULCH AND MN SEED TEMPORARY SEED & EROSION

CONTROL BLANKET

SILT FENCE

FLOTATION SILT CURTAIN

INLET PROTECTION

BIOROLL


					SEA
			\vdash		OL W
		\vdash			
3	FOR BIDDING	SJB	EAM	07/25/18	
2	90% DESIGN	SJB	EAM	06/12/18	
1	60% DESIGN	LNJ	EAM	12/20/17	
0	CONCEPT DESIGN	SJB	EAM	02/02/17	
REV	REVISION DESCRIPTION	DWN	APP	REV DATE	





LOWER SAND CREEK CORRIDOR RESTORATION LEGEND AND GENERAL NOTES


COON CREEK WATERSHED DISTRICT 12301 CENTRAL AVE NE, SUITE 100


APP'D DWG DATE FEB 2017 SJB LNJ EAM SCALE AS SHOWN G-102 3 1239-0093











Party Responsible for Long Term Operation and Maintenance of the Site - OWNER

Coon Creek Watershed District 12301 Central Ave NE, Suite 100 Blaine, MN 55434

Jon Janke, Operations and Maint. Coordinator 763-755-0975

jjanke@cooncreekwd.org

Party Responsible for Implementation of the SWPPP - CONTRACTOR (TBD)

Contractor	
Contact Name	
Phone	
Email	

Construction Dates: Fall 2018/Winter 2019

Project Description

The project work consists restoring a degraded section of lower Sand Creek. The project site stretches from Xeon Boulevard on the west to the Burlington Northern Santa Fe railroad on the east. Ground disturbing activities include clearing and harvesting of trees and brush, and stabilization of the stream banks and bottom with bioengineered materials including vegetated riprap toes, log toes with root wads, rock grade control structures, and riprap swales.

SURFACE AREA TABULATION

Total Disturbed Area	±1.0 acres
Existing Impervious Ar	ea ±0.0 acres
Proposed Impervious	Area ±0.0 acres
Net Impervious Area Ir	crease ±0.0 acres

EROSION AND SEDIMENT CONTROL PRACTICES

All exposed soil areas must have temporary erosion protection (erosion control blanket, mulch, seed) as soon as possible or within 7 days after the construction activity in that portion of the site has temporarily or permanently ceased.

CONTRACTOR shall implement appropriate construction phasing, vegetative buffer strips, and other construction practices that minimize erosion when practical. The normal wetted perimeter of any temporary or permanent drainage ditch that drains water from the construction site, or diverts water around the site, must be stabilized within 200 lineal feet from the property edge, or from the point of discharge to any surface water. Stabilization must be completed within 24 hours of connecting to a surface water. Pipe outlets must be provided with temporary or permanent energy dissipation within 24 hours of connection to a surface water.

The following measures will be taken as sediment control practices in order to minimize sediments from entering surface waters:

- 1. Installation of floating silt curtain around the banks at the downgradient extents of construction activity prior to disturbance. Floating silt curtain shall be installed as shown on Sheet D-102 and as directed by Engineer.
- 2. Installation of perimeter control in locations and quantities deemed adequate by the Engineer to protect sediment washing from restoration work activities.
- 3. Installation of a rock construction pad as shown on D-102. Install rock pad at the entrance to the access route to prevent sediment tracking onto paved public roads.
- 4. Haul offsite all excess soils as they are excavated. No stockpiling of soils onsite will be allowed.

Temporary Sediment Basin

Because this project will not disturb greater than 5 acres, a sedimentation basin is not required.

Dewatering

No dewatering is anticipated as part of this Proiect.

Final Stabilization

All areas disturbed by construction will be stabilized by installing erosion control blanket and receive seed according to the plans and specifications and within the specified vegetative time schedule.

Final stabilization will occur when the site has a uniform vegetative cover with a density of 70% over the entire disturbed area. All temporary synthetic erosion prevention and sediment control BMPs (such as silt fence) must be removed as part of the site final stabilization. All sediment must be cleaned out of conveyances and temporary sedimentation basins if applicable.

Notice of Termination (NOT) must be submitted within 30 days of final stabilization. Before Termination. revegetation establishment and coverage must meet the permit requirements.

Pollution Prevention Measures

Solid Waste

Solid waste, including but not limited to, collected asphalt and concrete millings, floating debris, paper, plastic, fabric, construction and demolition debris and other waste must be disposed of properly and must comply with MPCA disposal requirements.

Hazardous Materials

Hazardous materials, including but not limited to oil, gasoline, paint and any hazardous substance must be properly stored including secondary containments, to prevent spills, leaks or other discharge. Restricted access to storage areas must be provided to prevent vandalism. Storage and disposal of hazardous waste must be in compliance with MCPA regulations.

Washing of Construction Vehicles

External washing of trucks and other construction vehicles must be limited to a defined area of the site. Runoff must be contained and waste properly disposed of. No engine degreasing is allowed on site.

Amendments

Amend the SWPPP as necessary to address any changes in design, construction, operation, maintenance, weather or seasonal conditions that have a significant effect on discharge of pollutants to surface or underground waters; or to address concerns identified during inspections or investigations by OWNER or MPCA.

Record Retention

The SWPPP, all changes to it, and inspection and maintenance records must be kept on-site during construction. The OWNER must retain a copy of the SWPPP along with the following records for three (3) years after submittal of the Notice of Termination.

- 1. Any other permits required for the project;
- 2. Records of all inspection and maintenance conducted during construction:
- 3. All permanent operations and maintenance agreements that have been implemented, including all right of way, contract, covenants and other binding requirements regarding perpetual maintenance; and
- 4. All required calculations for design of the temporary and permanent stormwater management systems.


Inspections

The inspection log will be completed by the CONTRACTOR for the construction site. Inspections at the site will be completed as follows:

Once every seven (7) days during active construction and,

Within 24 hours after a rainfall event greater than 0.5 inches in 24 hours.

The individual performing inspections must be trained as required by part IV.E of the Permit. CONTRACTOR to provide OWNER with proof of training. Inspections must include stabilized areas, erosion prevention and sediment control BMPs, and infiltration areas. Corrective actions must be identified and date of correction must be noted as identified in Section IV.E. of the Permit.



IMPAIRED WATERS, SPECIAL WATERS, AND WETLANDS

This Project is not located within 1 mile of a special water.

This Project is located directly on an impaired water (see figure above): Sand Creek is impaired for E. coli, aquatic macroinvertebrate bioassessments. An EPA-approved TMDL has been completed for this water.

Because of the proximity of the project to an impaired water during construction, all exposed soil areas must be stabilized as soon as possible to limit soil erosion but in no case later than 7 days after the construction activity in that portion of the site has temporarily or permanently ceased.

This Project will temporarily impact wetlands. Adverse impacts will be mitigated onsite.


University of Minnesota

Louis H Sigtermans Minneapolis, MN

Design of Construction SWPPP


CERTIFICATION


In accordance with Part III.A.2 of the General Permit Authorization to Discharge Stormwater Associated with Construction Activity under the NPDES, the preparer of this document was trained under the University of Minnesota Erosion and Sediment Control Certification Program. Mr. Louis Sigtermans' certification in Design of SWPPP is valid through May 31, 2020.







ROJECT TITLE		SHEET TITLE					
SAND CREEK STABILIZATION		SWPPP					
			APP'D	DWG DATE	FEB	20	
COON CREEK WATERSHED DISTRICT	SJB	LNJ	EAM	SCALE A	S SH	OWN	
		NO.	SHEET NO.			REV	
12301 CENTRAL AVE NE, SUITE 100 BLAINE, MN 55434		1239-0093		EC-101			














4. SOAK CUTTING FOR 24 HOURS (MINIMUM) PRIOR TO INSTALLATION
5. DIP BOTTOM 4-6 INCHES IN ROOTING HORMONE
6. INSTALL THE CUTTING AND TAMP THE SOIL AROUND THE STAKE

LIVE STAKE HARVEST AND INSTALLATION

D-193

3 FOR BIDDING

2 90% DESIGN

1 60% DESIGN

0 CONCEPT DESIGN


REVISION DESCRIPTION

SJB EAM 07/25/18 SJB EAM 06/12/18

LNJ EAM 12/20/13

SJB EAM 02/02/1

DWN APP REV DATE



WENCK

Responsive partner. Exceptional outcomes.

PROJECT TITLE

LOWER SAND CREEK CORRIDOR RESTORATION

COON CREEK WATERSHED DISTRICT

12301 CENTRAL AVE NE, SUITE 100 BLAINE, MN 55434 DETAILS

SJB LNJ

1239-0093

APP'D DWG DATE FEB 2017

EAM SCALE AS SHOWN

3

D-103

1/3 STREAM WIDTH

ROOT WADS CAN DOUBLE AS ESCAPE LOGS
 ROOT WAD TO BE PLACED AS DIRECTED SO THAT ROOT END IS SUBMERGED BELOW THE NORMAL WATER LEVEL

SECTION VIEW

ESCAPE LOG (AMPHIBIOUS HABITAT STRUCTURE) - DETAIL 4

ESCAPE LOG-

BACK WATER POOL

ROOTS OPTIONAL