

# Middle Sand Creek Corridor Restoration

## Public Meeting

Coon Creek Watershed District

City of Coon Rapids

September 24<sup>th</sup>, 2019

Please sign in

# Agenda

*Please sign in*

Introductions

Project Presentation

Background

Project details

Discussion

Questions, Concerns, Suggestions

# Introductions



## Coon Creek WD

**Tim Kelly**

District Administrator

**Justine Dauphinais**

Water Quality

**Jon Janke**

Operations & Maintenance

**Dawn Doering**

Information & Education

**Ed Matthiesen** Engineer (Wenck)

**Seth Bossert** Engineer (Wenck)

## City of Coon Rapids

**Tim Himmer** Public Works Director

**Mark Hansen** City Engineer

**Gregg Engle** Park Supervisor

**Tom Schibilla** City Forester

## MN DNR

**Nick Proulx** Clean Water Specialist


# Background

## Sand Creek Drainage Area

Size: ~16 mi<sup>2</sup>

Suburban land use

Upstream area ditched  
for agriculture & now  
serves as stormwater  
conveyance system.



# Current Status of Sand Creek

Sand Creek does not meet state water quality standards for aquatic life or recreation

*Impaired under Section 303(d) of Federal Clean Water Act*

## Stressors:

Excess Sediment

Excess Phosphorus

Poor Habitat

Altered Hydrology



# Current Status of Sand Creek

Sand Creek does not meet State water quality standards for aquatic life or recreation

Impaired under Section 303(d) of Federal Clean Water Act

## Causes:


Urban stormwater runoff

Stream bank erosion




# Past Projects to address urban stormwater

- ❖ Constructed new stormwater pond at Xeon St.
- ❖ Modified 2 pond outlets to hold more water
- ❖ Installed 25 Rain Gardens
- ❖ Stormwater regulations



# Past Projects to address bank erosion/ poor habitat




## 2018 Lower Sand Creek Corridor Restoration



# Middle Sand Creek Area

*Location: Railroad to Kumquat Pedestrian Bridge*



# Proposed Middle Sand Creek Project

## Goals:

1. Reduce sediment & nutrient pollution from streambank erosion

2. Enhance habitat for native species

3. Lessen impacts of altered hydrology, while providing conveyance

# 1. Reduce excess sediment/phosphorus

Stabilize eroding banks using 3 methods:

Vegetated Rock Riprap



# 1. Reduce excess sediment/phosphorus

Stabilize eroding banks using 3 methods:

Vegetated Rock Riprap



Lower Sand Creek Example

# 1. Reduce excess sediment/phosphorus

Stabilize eroding banks using 3 methods:

Vegetated Rock Riprap

Re-grading & seeding



# 1. Reduce excess sediment/phosphorus

Stabilize eroding banks using 3 methods:

Vegetated Rock Riprap

Re-grading & seeding



Lower Sand Creek Example


# 1. Reduce excess sediment/phosphorus

Stabilize eroding banks using 3 methods:

Vegetated Rock Riprap



Re-grading & seeding

Woody materials: log toes, root wads, toe wood



# 1. Reduce excess sediment/phosphorus

Woody materials: log toes, root wads, toe wood





# 1. Reduce excess sediment/phosphorus

Woody materials: log toes, root wads, toe wood



Lower Sand Creek Example

## 2. Enhance habitat for native species

Incorporating wood in bank stabilization practices

Adding in-stream structures: cross vanes, rock riffles, J-hooks



## 2. Enhance habitat for native species

Incorporating wood in bank stabilization practices

Adding in-stream structures: cross vanes, rock riffles, J-hooks

Managing vegetation: Tree thinning, buckthorn removal, planting native species



# 3. Lessen impacts of altered hydrology

(while providing conveyance & promoting long term channel stability)

Channel meandering


Floodplain reconnection

“Natural Channel Design”




# Proposed Middle Sand Creek Corridor Project

- ❖ Upstream reach: stabilize banks in place + add in-channel habitat elements
- ❖ Downstream reach: Natural channel design




# Proposed Middle Sand Creek Corridor Project

Extent of tree-thinning, 26% of surveyed trees



1947



# Project Timeline

Spring-Fall 2019: Planning

Winter-Spring 2019: Phase 1 construction

Spring-Summer 2019: Site restoration/ vegetation establishment

Fall-Winter 2020: Phase 2 construction

Spring-Summer 2020: Site restoration/ vegetation establishment

Fall 2020-2021: Continued invasive species control and maintenance



# Middle Sand Creek Corridor Project

Cost: ~\$1,000,000

**NO DIRECT COST to you**

*MN Clean Water Fund grant: \$382,772*

*Federal 319 grant: \$291,000*

*Coon Creek WD: ~\$400,000*



# Additional project elements

Newsletter & webpage updates: [www.cooncreekwd.org/MiddleSandCreekResto](http://www.cooncreekwd.org/MiddleSandCreekResto)

Interpretive signage

Interactive “Watershed walks”

Follow-up monitoring & maintenance



# Issues & Concerns

- ❖ Maintain wild & natural character of area
  - Concentrate tree removal to maintain untouched buffer
  - Use pollinator-friendly native plant species
  - bird nesting boxes
- ❖ Heavily-used trail corridor
  - Temporary spot closures
  - Safety
  - Lack of dog waste disposal stations
- ❖ Construction disturbance/ noise
- ❖ Storm damage/ resiliency/ Long-term maintenance

# Questions, Concerns, Suggestions?

Thank you!



## Contact:

Justine Dauphinais & Jon Janke

763-755-0975

[www.cooncreekwd.org/MiddleSandCreekResto](http://www.cooncreekwd.org/MiddleSandCreekResto)