

Permit Application Review Report
Date: 9/9/2026**Board Meeting Date: 9/14/2026**
Agenda Item: 15Applicant/Landowner:PGA Tour
Attn: Milan Moore
1 PGA Tour Blvd
Ponte Vedra Beach, FL 32082**Project Name:** TPC Blaine Golf Course Bunker Rehab Project**Project PAN:** P-26-051**Project Purpose:** Regrading and reshaping golf course bunkers**Project Location:** Holes 7, 11, 13 & 16, 11444 Tournament Players Parkway, Blaine**Site Size:** size of disturbed area - 3.0 acres; size of regulated impervious surface – 0 acres**Applicable District Rule(s):** Rule 2, Rule 4

Recommendation: Approve with 2 Conditions and 0 Stipulations

Description: The TPC gold course is proposing modifications (reshaping and regrading) to several sand bunkers within the TPC Golf Course. The project will disturb 3 acres. The area drains to County Ditch 41. The relevant water resource concern is Soils & Erosion Control (District Rule 4). See attached Figure 1: Project Location.

Conditions to be Met Before Permit Issuance:Rule 2.7 – Procedural Requirements

1. Provide a performance escrow in the amount of \$12,000.00 and execute a signed escrow agreement.

Rule 4.0 – Soils and Erosion Control

2. Update the SWPPP to provide the following:
 - a. Include temporary and permanent stabilization specifications.
 - b. Include a note to position portable toilets so they are secure.
 - c. Provide a concrete washout standard detail.

Stipulations: None**Exhibits:**

Exhibit Type	Exhibit Author	Signature Date	Received Date
Construction Plans	Kimley Horn	08/18/2026	08/18/2026

Findings

Fees and Escrows (Rule 2.7):

The applicant has submitted a \$2,000.00 review and inspection fee and deposit which corresponds with the sum of fees associated with Rule 4.0 (\$2,000 for 3.0 acres of land disturbance proposed).

The applicant will be required to submit a performance escrow in the amount of \$12,000.00. This corresponds to \$4,000/acre of disturbance (3.0 acres of land disturbance proposed).

Stormwater Management (Rule 3.0):

The proposed project does not create a cumulative total of 10,000 sf or more of new or fully reconstructed impervious surface, or 5,000 sf or more of new or fully reconstructed impervious surface for non-residential or multifamily residential within one mile of and draining to an impaired water. The proposed project is not a public linear project where the sum of the new and fully reconstructed impervious surface is equal to one or more acres. Stormwater Management standards do not apply.

Soils and Erosion Control (Rule 4.0)

Rule 4.0 applies to the proposed project because it includes land disturbing activities of 1 acre or more.

The proposed project drains to County Ditch 41. The soils affected by the project are Rifle and do not have a soil erodibility factor of 0.15 or greater. Disturbed areas are proposed to be stabilized within 7 days, as required. The proposed erosion and sediment control plan includes perimeter control and street sweeping. The erosion control plan does not meet District requirements because concrete washout detail and stabilization specifications have not been provided, and portable toilets are not proposed to be positioned to prevent tipping. The site does require an NPDES permit. See attached Figure 2: Soils and Erosion Control Plan.

Wetlands (Rule 5.0)

The proposed project does not include activities which result in the filling, draining, excavating, or otherwise altering the hydrology of a wetland. Rule 5.0 does not apply.

Floodplain (Rule 6.0)

The proposed project does not include land disturbing activities within the floodplain as mapped and modeled by the District. Rule 6.0 does not apply.

Drainage, Bridges, Culverts, and Utility Crossings (Rule 7.0)

The proposed project does not include land disturbing activities which construct, improve, repair, or alter the hydraulic characteristics of a bridge profile control or culvert structure on a creek, public ditch, or major watercourse. The proposed project does not include land disturbing activities which involve a pipeline or utility crossing of a creek, public ditch, or major watercourse.

The proposed project does not include land disturbing activities which construct, improve, repair or alter the hydraulic characteristics of a conveyance system that extends across two or more parcels of record not under common ownership and has a drainage area of 200 acres or greater. Rule 7.0 does not apply.

Buffers (Rule 8.0)

The proposed project does not include a land disturbing activity on land adjacent or directly contributing to a Public Water, Additional Waters, High or Outstanding Ecological Value Waters, a Public Ditch, or Impaired Waters/waters exceeding state water quality standards. Rule 8.0 does not apply.


Variances (Rule 10.2)

The proposed project is not requesting a variance from the District's rules, regulations, and policies. Rule 10.2 does not apply.

Figure 1: TPC Bunker Rehabilitation Project Location



9/8/2026



An aerial photograph of a golf course with overlaid design lines. A specific area, labeled with a large black '#7', is highlighted with a thick yellow border and a pink interior. This area is situated between a large, dark water feature on the right and a cluster of smaller ponds and sand traps on the left. The map includes various dashed and solid lines representing proposed or existing boundaries, as well as small circular icons indicating tree locations. The background shows the natural terrain, including grass, trees, and some surrounding infrastructure like roads and buildings.

EROSION CONTROL PLAN NOTES


1. THE STORM WATER POLLUTION PREVENTION PLAN ("SWPPP") IS COMPOSED OF THE PROJECT'S SWPPP MANUAL AND ATTACHED APPENDICES. ATTACHMENTS INCLUDED IN THE SPECIFICATIONS OF THE SWPPP, PLUS THE PERMIT AND ALL OTHER APPLICABLE REGULATIONS.
2. ALL CONTRACTORS AND SUBCONTRACTORS INVOLVED WITH LAND DISTURBANCE ACTIVITIES SHALL OBTAIN A COPY OF THE SWPPP AND NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) GENERAL PERMIT, AND BECOME FAMILIAR WITH THEIR CONTENTS.
3. BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS SHALL CONFORM TO FEDERAL, STATE AND LOCAL REQUIREMENTS FOR EROSION CONTROL AND SEDIMENTATION. ADDITIONAL CONTROLS AS DIRECTED BY THE PERMITTING AGENCY, ENGINEER OR OWNER.
4. SITE ENTRY AND EXIT LOCATIONS SHALL BE MAINTAINED IN A CONDITION THAT WILL PROTECT EXISTING VEGETATION FROM DAMAGE. ANY VEHICLES THAT ENTER OR LEAVE THE SITES MUST BE CLEANED OF MUD AND DEBRIS BEFORE LEAVING. WHEN WASHING IS REQUIRED TO REMOVE SEDIMENT FROM TIRE ENTRANCE ONTO A PUBLIC ROADWAY, IT SHALL BE DONE AT AN APPROVED LOCATION. ANY FINES IMPOSED FOR DISCHARGING SEDIMENT ONTO A PUBLIC ROADWAY SHALL BE PAID BY THE PARTY RESPONSIBLE FOR THE VIOLATION.
5. TEMPORARY SEEDING OR OTHER APPROVED METHODS OF STABILIZATION SHALL BE INITIATED WITHIN 7 DAYS OF THE LAST DISTURBANCE ON ANY AREA OF THE SITE.
6. THE CONTRACTOR SHALL MINIMIZE LAND DISTURBANCE AND CLEARING TO THE MAXIMUM EXTENT POSSIBLE, AS WELL AS PROVIDE EROSION CONTROL MEASURES TO PREVENT EROSION.
7. THE CONTRACTOR SHALL DENOTE ON THE PLAN THE TEMPORARY PARKING AND STORAGE AREA WHICH SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AND CLEANING AREA. TEMPORARY PARKING AND STORAGE AREAS FOR LOADING/PORTRAITABLE FACILITIES, OFFICE TRAILERS, AND TOILET FACILITIES.
8. ALL WASH WATER FROM THE CONSTRUCTION SITE (CONCRETE TRUCKS, VEHICLE CLEANSING, EQUIPMENT CLEANSING, ETC.) SHALL BE DETAINED AND PROPERLY TREATED BEFORE DISPOSAL.
9. SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOATATION BOOMS SHALL BE MAINTAINED ON SITE OR READILY AVAILABLE TO CONTAIN AND CLEAN-UP FUEL OR OIL SPILLS, OILS AND LEAKS.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DUST CONTROL ON SITE. THE USE OF MOTOR VEHICLES AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION IS PROHIBITED.
11. RUBBER TIRMS, GARBAGE LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEALED CONTAINERS. MATERIALS SHALL BE PREVENTED FROM LEAVING THE PROPERTY THROUGH THE DRIVE/WAY OR STORM WATER DISCHARGE INTO DRAINAGE DITCHES OR WATERS OF THE STATE.
12. STAGING AREAS, STOCKPILES, SPILLS, ETC. SHALL BE LOCATED OUTSIDE OF DRAINAGE BASINS AND DOWNSTREAM OF ANY EXISTING OR PROPOSED STORMWATER STABILIZATION STRUCTURES SUCH AS PERMETTER EROSION CONTROL BMPs, SEEDING, OR CRIPPLES, AS NECESSARY TO PREVENT POLLUTION.
13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RE-STABILIZING ANY EROSION CONTROL BMP DISTURBED DURING CONSTRUCTION OPERATIONS. NOTIFY THE OWNERS IMMEDIATELY IF ANY EROSION CONTROL MEASURES ARE DAMAGED OR DESTROYED. MEASURES THAT MAY LEAD TO UNAUTHORIZED DISCHARGE OF STORM WATER POLLUTANTS UNAUTHORIZED POLLUTANTS INCLUDE BUT ARE NOT LIMITED TO EXCESS COARSE AGGREGATE, COARSE SAND, COARSE SILTS, CLAYS, OILS, GREASES, FUELS, LUBRICANT OILS, PESTICIDES, AND SOLID WASTE MATERIALS.
14. EROSION CONTROL BMPs SHOWN ON THESE PLANS SHALL BE INSTALLED PRIOR TO THE START OF ANY LAND-DISTURBING ACTIVITIES ON THE PROJECT, INITIATED AS SOON AS PRACTICABLE.
15. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR COMPLYING WITH THE REQUIREMENTS OF ANY APPLICABLE ORDINANCES, RULES, REGULATIONS, AND STANDARDS, AS WELL AS APPLICABLE LAWS AND REGULATIONS FOR THE DURATION OF CONSTRUCTION.
16. THE CONTRACTOR SHALL FIELD ADJUST AND/OR PROVIDE ADDITIONAL EROSION CONTROL MEASURES TO PREVENT POLLUTION. THE CONTRACTOR SHALL MAINTAIN RECORDS OF THE CONSTRUCTION SITE LOG AND RECORD ANY ADJUSTMENTS AND DEVIATIONS FROM THE EROSION CONTROL PLAN WITHIN THE SAME DOCUMENTS STORED IN THE JOB SITE TRAILER.

SWPPP UPDATES & AMENDMENTS

THE CONTRACTOR MUST UPDATE THE SWPPP BY NOTING CHANGES TO THE SWPPP MAPS IN THE JOB SITE BINDER TO REFLECT THE PROGRESS OF CONSTRUCTION ACTIVITIES AND GENERAL CHANGES TO THE SWPPP. UPDATES TO THE SWPPP SHALL BE MADE BY THE CONTRACTOR. THE CONTRACTOR SHALL MAKE UPDATES SHALL BE MADE DAILY DURING CONSTRUCTION PROGRESS DESCRIBED IN THE SWPPP. UPDATES TO THE SWPPP SHALL BE MADE BY THE CONTRACTOR. THE CONTRACTOR SHALL MAKE UPDATES TO THE SWPPP MAPS IN THE JOB SITE BINDER. TEMPORARY PARKING & LAYDOWN AREAS, PORTA-POTTY, AND OTHER CONSTRUCTION RELATED FACILITIES CAN HAVE IMPACT STORMWATER RUNOFF.

1. EXISTING PERIMETER EROSION CONTROL (I.E. SILT FENCE) AND INLET PROTECTION AT EXISTING STORMWATER INLETS.
2. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT.
3. PREPARE TEMPORARY PARKING AND STORAGE AREA.
4. CONSTRUCT AND STABILIZE DIVERSIONS.
5. CLEAR AND GRUB THE SITE.
6. BEGIN MASS SITE GRADING AND ROUGH GRADE SITE SUFFICIENTLY TO ESTABLISH EXPOSED DRAINAGE PATTERNS.
7. TEMPORARILY SEED THROUGHOUT CONSTRUCTION. DISTURBED AREAS THAT WILL BE INACTIVE FOR 14 DAYS OR MORE OR AS REQUIRED BY THE NPDES AND/OR CITY GRADING PERMIT(S).

NOTE: THE SEQUENCE OF CONSTRUCTION IS INTENDED TO CONVEY THE GENERAL CONCEPTS OF THE EROSION CONTROL DESIGN AND SHOULD NOT BE RELIED UPON FOR CONSTRUCTION PURPOSES. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETAILED PHASING AND CONSTRUCTION SEQUENCING NECESSARY TO CONSTRUCT THE PROPOSED IMPROVEMENTS. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IN WRITING IMMEDIATELY, PRIOR TO AND/OR DURING CONSTRUCTION IF ANY ADDITIONAL INFORMATION ON THE CONSTRUCTION SEQUENCE IS NECESSARY.



Know what's below.
Call before you dig.

SHEET NUMBER C201	TPC BLAINE GOLF COURSE BUNKER REHAB PREPARED FOR TPC TWIN CITIES BLAINE MN	EROSION AND SEDIMENT CONTROL PH1 PLAN	KHA PROJECT 100-00001 DATE 08/18/2008 SCALE AS SHOWN DESIGNED BY ALC DRAWN BY AMZ	INFORMATION REPORT WAS PREPARED BY THE KIMLEY-HORN AND ASSOCIATES, INC. 3200 KIMLEY-HORN AND ASSOCIATES, INC. 707 EUSTIS ST. SUITE 100, FT. PALL, MN 55114 PHONE: 651-454-4197 WWW.KIMLEY-HORN.COM	NO. _____ REVISIONS _____ DATE _____ BY _____
			CHECKED BY DATE 08/18/2008 MR. HQ. #2969		

#11




PHASE I BMP QUANTITIES	
SILT FENCE	±1,610 LF
BIO ROLL	±4,580 LF

1. THE STORM WATER POLLUTION PREVENTION PLAN ("SWPPP") IS COMPOSED OF THE EROSION CONTROL PLAN, THE STANDARD DETAILS, THE PLAN NARRATIVE, ATTACHMENTS AND A TRUE COPY OF THE PERMIT. THE CONTRACTOR SHALL MAINTAIN THE PLAN AND ALL SUBSEQUENT REPORTS AND RELATED DOCUMENTS.
2. ALL CONTRACTORS AND SUBCONTRACTORS INVOLVED WITH LAND DISTURBING ACTIVITIES SHALL BE REQUIRED TO REGISTER WITH THE STATE OF TEXAS AND OBTAIN A STATE EROSION CONTROL SYSTEM (NPOES) GENERAL PERMIT, AND BECOME FAMILIAR WITH THEIR CONTENTS.
3. BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS SHALL CONFORM TO FEDERAL, STATE AND LOCAL REQUIREMENTS AND SHALL BE APPROVED BY THE PERMITTING AGENCY. ADDITIONAL CONTROLS AS DIRECTED BY THE PERMITTING AGENCY, ENGINEER OR OWNER.
4. SITE ENTRY AND EXIT LOCATIONS SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OF MATERIALS, DEBRIS, AND SEDIMENT OFF-SITE. TRACKING SHALL BE SPILLED, DROPPED, WASHED, OR TRACKED INTO A PUBLIC ROADWAY FROM THE CONSTRUCTION SITE. TRACKING SHALL BE REMOVED IMMEDIATELY WHEN WASHING IS REQUIRED TO REMOVE SEDIMENT, TRACKS TO ENTRANCE INTO A PUBLIC ROADWAY. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PREVENT TRACKING OF MATERIALS INTO AN APPROVED SEGMENT BASIN. ANY FINES IMPOSED FOR DISCHARGING SEDIMENT INTO A PUBLIC RIGHT OF WAY SHALL BE PAID BY THE CONTRACTOR.
5. TRUCKS, TRAILERS, AND EQUIPMENT SHALL BE WASHED AND CLEANED PRIOR TO BEING INITIATED WITHIN 7 DAYS OF THE LAST DISTURBANCE ON ANY AREA OF THE SITE.
6. THE CONTRACTOR SHALL MINIMIZE LAND DISTURBANCE AND CLEANING TO THE MAXIMUM EXTENT PRACTICAL, OR AS REQUIRED BY THE GENERAL PERMIT.
7. CONTRACTOR SHALL DENOTE ON THE PLAN THE TEMPORARY PARKING AND STORAGE AREAS. THE CONTRACTOR SHALL ALSO IDENTIFY THE EXISTING CONCERNANCE AND CONCERN AREA, EMPLOYEE PARKING AREA, AND AREA FOR LOCATING PORTABLE FACILITIES. OFFICE, STORAGE, AND TOILET FACILITIES SHALL BE LOCATED OUTSIDE OF THE EROSION CONTROL AREA.
8. ALL WASH WATER FROM THE CONSTRUCTION SITE (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE OBTAINED AND PROPERLY TREATED BEFORE DISCHARGE.
9. SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS SHALL BE MAINTAINED ON SITE OR READILY AVAILABLE TO OBTAIN AND CLEANUP OIL AND GREASE FROM RAIN AND LEAK.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DUST CONTROL ON SITE. THE USE OF MISTERS, ROTARY AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION SHALL BE PROHIBITED.
11. RUBBISH, TRASH, GARBAGE, LIDS, OR OTHER SUCH MATERIALS SHALL BE DISPOSED INTO SEALED CONTAINERS. MATERIALS SHALL BE PREVENTED FROM LEAVING THE PROJECT THROUGH THE ACTION OF WIND OR STORM WATER DISCHARGE INTO DRAINAGE CHANNELS OR DRAINAGE OF THE PROJECT.
12. STAGING AREAS, STOCKPILES, SPILLS, ETC. SHALL BE LOCATED OUTSIDE OF DRAINAGE WAYS SUCH THAT STORM WATER RUNOFF WILL NOT BE ADVERSELY AFFECTED. PROVIDED THAT THE CONTRACTOR SHALL MAINTAIN EROSION CONTROL BMPs, SEDIMENT, OR OTHER COVERING AS NECESSARY TO PREVENT EROSION.
13. CONTRACTOR SHALL BE RESPONSIBLE FOR RE-ESTABLISHING ANY EROSION CONTROL MEASURES THAT ARE DAMAGED OR DESTROYED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DEFICIENCIES IN THE ESTABLISHED EROSION CONTROL MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STORAGE OF POLLUTANTS. UNAUTHORIZED POLLUTANTS INCLUDE (BUT ARE NOT LIMITED TO) EXCESS FERTILIZER, EXCESS MINERAL OILS, EXCESS GREASE, EXCESS OIL, EXCESS WATER, EXCESS LUBRICANT OILS, PESTICIDES, AND SOLID WASTE MATERIALS.
14. EROSION CONTROL BMPs SHOWN ON THESE PLANS SHALL BE INSTALLED BEFORE THE START OF ANY LAND DISTURBING ACTIVITIES ON THE PROJECT, AND INITIATED AS SOON AS PRACTICABLE.
15. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR COMPLYING WITH THE REQUIREMENTS SET FORTH IN THE SWPPP AND THE EROSION CONTROL PLAN, AND SHALL BE IN COMPLIANCE WITH APPLICABLE LAWS AND REGULATIONS FOR THE DURATION OF CONSTRUCTION.
16. THE CONTRACTOR SHALL FIELD ADJUST AND/OR PROVIDE ADDITIONAL EROSION CONTROL BMPs AS NEEDED TO PREVENT EROSION AND OFF-SITE SEDIMENT DISCHARGE FROM THE PROJECT. THE CONTRACTOR SHALL LOCATE AND MAINTAIN THE EROSION CONTROL BMPs AS APPROVED EROSION CONTROL PLANS WITHIN THE SWPPP DOCUMENTS STORED IN THE PROJECT OFFICE.

1. INSTALL PERIMETER EROSION CONTROL (I.E. SILT FENCE) AND INLET PROTECTION AT EXISTING STORMWATER INLETS.
2. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT. PREPARE TEMPORARY PARKING AND STORAGE AREA.
3. CONSTRUCT AND STABILIZE DIVERSIONS.
4. CLEAR AND GRUB THE SITE.
5. BEGIN MASS SITE GRADING AND ROUGH GRADE SITE SUFFICIENTLY TO ESTABLISH PROPOSED DRAINAGE PATTERNS.
6. TEMPORARILY SEED, THROUGHOUT CONSTRUCTION, DISTURBED AREAS THAT WILL BE INACTIVE FOR 14 DAYS OR MORE OR AS REQUIRED BY THE NPDES AND/OR CITY (RAINING PERMITS).


NOTE: THE SEQUENCE OF CONSTRUCTION IS INTENDED TO CONVEY THE GENERAL CONCEPT OF THE EROSION CONTROL DESIGN AND SHOULD NOT BE RELIED UPON FOR CONSTRUCTION PURPOSES. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETAILED PHASING AND CONSTRUCTION SEQUENCING NECESSARY TO CONSTRUCT THE PROPOSED IMPROVEMENTS. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IN WRITING IMMEDIATELY, PRIOR TO AND/OR DURING CONSTRUCTION IF ANY ADDITIONAL INFORMATION ON THE CONSTRUCTION SEQUENCE IS NECESSARY.



Know what's **below**.
Call before you dig.

[illegible]

K:\TWC_LDEV\TPC of Minnesota, Inc\Blaine Golf Course Bunker Rehab Project\3 Design\CAD\PlanSheets\C3-EROS PH1 PLAN.dwg August 18, 2026 - 11:34am



EROSION CONTROL PLAN NOTES

- ### PHASE 1 SEQUENCE OF CONSTRUCTION

1. INSTALL PERIMETER EROSION CONTROL (I.E. SILT FENCE) AND INLET PROTECTION AT EXISTING STORMWATER INFLOW.
2. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT.
3. PREPARE TEMPORARY PARKING AND STORAGE AREA.
4. CONSTRUCT AND STABILIZE DIVERSIONS.
5. CLEAR AND GRUB THE SITE.
6. BEGIN MASS SITE GRADING AND ROUGH GRADE SITE SUFFICIENTLY TO ESTABLISH PROPOSED DRAINAGE PATTERNS.
7. TEMPORARY SEED, TURF OR TOP SOIL CONSTRUCTION, DISTURBED AREAS THAT WILL BE INACTIVE FOR 14 DAYS OR MORE OR AS REQUIRED BY THE NPDES AND/OR CITY GRADING PERMIT(S).

NOTE: THE SEQUENCE OF CONSTRUCTION IS INTENDED TO CONVEY THE GENERAL CONCEPTS OF THE EROSION CONTROL DESIGN AND SHOULD NOT BE RELIED UPON FOR CONSTRUCTION PURPOSES. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETAILED PHASING AND CONSTRUCTION SEQUENCING NECESSARY TO CONSTRUCT THE PROPOSED IMPROVEMENTS. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IN WRITING IMMEDIATELY, PRIOR TO AND/OR DURING CONSTRUCTION IF ANY ADDITIONAL INFORMATION ON THE CONSTRUCTION SEQUENCE IS NECESSARY.



TPC BLAINE GOLF COURSE BUNKER REHAB PREPARED FOR TPC TWIN CITIES BLAINE MN	SHEET NUMBER C203	EROSION AND SEDIMENT CONTROL PH1 PLAN	KMA PROJECT 16139701 DATE 08/01/2014 SCALE AS SHOWN DESIGNED BY ALC DRAWN BY AMZ CHECKED BY DATE 08/01/2014 KMA NO. 47969	I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY CLOSE PERSONAL SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  KIMLEY-HORN AND ASSOCIATES, INC. 200 KENYON AVENUE 707 EAST ST. SUITE 100, ST. PAUL, MN 55114 PHONE 651-654-4197 WWW.KIMLEY-HORN.COM	No.	REVISIONS	DATE	BY

K:\TWC_LDEV\TPC of Minnesota, Inc\Blaine Golf Course Bunker Rehab Project\3 Design\CAD\PlanSheets\C3-EROS PH1 PLAN.dwg August 18, 2026 - 11:34am



SHEET NUMBER	TPC BLAINE GOLF COURSE		EROSION AND SEDIMENT CONTROL PH1 PLAN	KHA PROJECT 181000 DATE 08/10/2008 SCALE AS SHOWN DESIGNED BY ALC DRAWN BY AMZ CHECKED BY AMZ DATE 08/10/2008 MC. NO. 47969	INVESTIGATION REPORT PREPARED BY KIMLEY-HORN AND ASSOCIATES, INC. 2008 KIMLEY-HORN AND ASSOCIATES, INC. 707 EILEY ST. SUITE 100, ST. PAUL, MN 55114 PHONE: 651-654-6197 WWW.KIMLEY-HORN.COM	NO. OF REVISIONS DATE BY
	TPC BLAINE BUNKER REHAB PREPARED FOR TPC TWIN CITIES MN					